



WALL

	EXISTING CONSTRUCTION
	NEW CONSTRUCTION

FIT PLAN LEGEND

PROGRAM TYPE	COUNTS	COMMENTS
BENCHING WORKSTATION	119	24" x 48"
SMALL CONFERENCE	3	
MEDIUM CONFERENCE	1	
LOUNGE CONFERENCE	2	
PHONE ROOM	4	
PANTRY	1	
STORAGE ROOM	1	
SERVER LAB	1	

FIT PLAN KEYNOTES

NOTE	DESCRIPTION
1	EXTEND TILE FLOOR FROM PANTRY INTO THIS AREA
2	PROVIDE TRENCH FOR ELECTRICAL FOR CONFERENCE TABLE
3	INSTALL NEW WALL AND DOORS AT THESE LOCATIONS TO CREATE A SMOKE BARRIER DUE TO ELEVATORS NOT BEING PRESSURIZED
4	RELOCATE DOOR AND FRAME TO THIS LOCATION
5	PROVIDE A (2) DEDICATED CIRCUIT (15AMP DRAW) FOR (2) COFFEE MAKERS ALONG WITH A CIRCUIT (3AMP DRAW) FOR WATER DISPENSER (2) 5-20R SINGLE OUTLETS
6	(2) DEDICATED FRIDGE CIRCUITS
7	(2) DEDICATED MICROWAVE OUTLET (15AMP DRAW)
8	(1) DEDICATED DISHWASHER OUTLET
9	PROVIDE FULL HEIGHT GWB BETWEEN THESE (2) ROOMS

SCOPE OF WORK NOTES"

- ALL CONFERENCE ROOMS TO BE FRAMELESS GLASS DOORS (INCLUDES THE LOUNGES)
- PHONE ROOMS TO BE WOOD DOORS WITH HOLLOW METAL FRAMES AND FULL GLASS PANEL INSERTS
- (3) MINI PHONE ROOMS TO HAVE RETRACTABLE DOORS
- PROVIDE POWER AND BLOCKING FOR TELEVISIONS AT ALL PHONE ROOMS, LOUNGES, CONFERENCES & AT PANTRY
- PROVIDE (3) WATERLINES FOR (2) COFFEE MAKERS AND WATER DISPENSER
- PROVIDE A POWER OUTLET AT EACH COLUMN LOCATION
- LAB POWER & HVAC TO BE: (14) SEPARATE 20AMP CIRCUIT BREAKERS FOR NEMA- 20 OUTLETS DOUBLE DUPLEX. HVAC TO HAVE SEPARATE ZONE AND CONTROL FOR LAB ONLY

