ALTA/NSPS LAND TITLE SURVEY
OF
Carollo - Wheeling IL



VICINITY MAP
NOT TO SCALE

AREA

139,341 SQ. FT.

3.1988 ACRES

FLOOD HAZARD NOTE

PART OF THIS PROPERTY IS IN A SPECIAL FLOOD HAZARD AREAS WITH BASE FLOOD ELEVATION OR DEPTH (ZONE AE) AND IN AN AREA OF 0.2% ANNUAL CHANCE FLOOD HAZARD, AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTH LESS THAN ONE FOOT OR WITH DRAINAGE AREAS OF LESS THAN ONE SQ. MILE (ZONE X) AS DEFINED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY'S FLOOD INSURANCE RATE MAP OF COOK COUNTY, ILLINOIS AND INCORPORATED AREAS (COMMUNITY PANEL NO. 17031C00681J) AND LOMR 19-051451P, EFFECTIVE 03/04/21.

FLOOD MAP

PARCEL 1:

LOT 1 & 2 IN MARTIN W. KNITTEL'S SUB OF THE NORTH 60 FEET OF LOT 65, LOTS 1 TO 7 LOTS 11 TO 17 OF PETER KNITTEL'S ADDITION TO HUNTERSVILLE, TOGETHER WITH THAT PART OF THE EAST 385.2 FEET OF LOT 3 OF THE SUBDIVISION OF THE KNITTEL FARM LYING NORTH OF THE SOUTH LINE OF TOWN STREET EXTENDED IN SECTIONS 3 & 10, TOWNSHIP 42 NORTH, RANGE 11 EAST OF THE THIRD PRINCIPAL MERIDIAN, EXCEPT THAT PART THEREOF TAKEN FOR PUBLIC STREET IN PLAT REGISTERED AS DOCUMENT 3234098, AND ALSO (EXCEPT THAT PART OF LOT 1 CONVEYED TO THE ILLINOIS DEPARTMENT OF TRANSPORTATION RECORDED SEPTEMBER 23, 2015 AS DOCUMENT 1526646074), IN COOK COUNTY, ILLINOIS.

PARCEL 2:

THAT PART OF LOT 2 IN OWNER'S DIVISION OF PART OF THE SOUTHEAST 1/4 OF SECTION 3 AND PART OF THE NORTHEAST 1/4 OF SECTION 10, TOWNSHIP 42 NORTH, RANGE 11, EAST OF THE THIRD PRINCIPAL MERIDIAN, IN COOK COUNTY, ILLINOIS, (ACCORDING TO THE PLAT THEREOF REGISTERED IN THE OFFICE OF THE REGISTRAR OF TITLES OF COOK COUNTY, ILLINOIS, AS DOCUMENT NUMBER 514017), WHICH LIES SOUTH OF A LINE 57.79 FEET SOUTH OF AND PARALLEL WITH THE NORTH LINE OF THE NORTHEAST 1/4 OF SAID SECTION 10, LYING NORTH OF A LINE 600.0 FEET NORTH OF AND PARALLEL WITH THE SOUTH LINE OF SAID LOT 2 AND LYING WEST OF A LINE 746.40 FEET WEST OF AND PARALLEL WITH THE EAST LINE OF THE NORTHEAST 1/4 OF SAID SECTION 10; EXCEPTING THEREFROM THAT PART BEING DEDICATED FOR WHEELING ROAD, DESCRIBED AS FOLLOWS: BEGINNING AT A POINT ON THE WEST LINE OF SAID LOT 2 SAID POINT BEING 600.0 FEET NORTH OF THE SOUTH LINE OF SAID LOT 2; THENCE EAST PARALLEL WITH THE SOUTH LINE OF LOT 2, A DISTANCE OF 40.0 FEET; THENCE NORTHERLY TO A POINT OF THE NORTH LINE OF SAID LOT 2, SAID POINT BEING 46.0 FEET EAST OF THE MOST WEST-NORTHWEST CORNER OF LOT 2; THENCE SOUTH ALONG THE WEST LINE OF SAID LOT 2 TO THE POINT OF BEGINNING; IN COOK COUNTY, ILLINOIS.

PARCEL 3:

THE EAST 80 FEET OF THE FOLLOWING DESCRIBED PARCELS OF REAL ESTATE, TAKEN AS A TRACT: THAT PART OF LOT 2 IN OWNER'S DIVISION OF THE PART OF THE SOUTHEAST 1/4 OF SECTION 3 AND THE NORTHEAST 1/4 OF SECTION 10, TOWNSHIP 42 NORTH, RANGE 11 EAST OF THE THIRD PRINCIPAL MERIDIAN, (ACCORDING TO THE PLAT THEREOF REGISTERED IN THE OFFICE OF THE REGISTRAR OF TITLES OF COOK COUNTY, ILLINOIS, AS DOCUMENT 514017), LYING SOUTH OF A LINE 33 FEET SOUTH OF AND PARALLEL WITH THE CENTER LINE OF DUNDEE ROAD, AND LYING WESTERLY OF A LINE DESCRIBED AS FOLLOWS: COMMENCING AT A POINT IN SAID LOT 2 ON A LINE 30 FEET NORTH OF THE CENTER LINE OF TOWN STREET AND 666.4 FEET WEST OF THE EAST LINE OF THE NORTHEAST 1/4 OF SAID SECTION 10; THENCE NORTH ALONG A LINE PARALLEL WITH THE EAST LINE OF THE NORTHEAST 1/4 OF SAID SECTION 10, A DISTANCE OF 780.30 FEET TO THE NORTH LINE OF SAID SECTION; THENCE CONTINUING ALONG SAID LINE WHICH IS 666.4 FEET WEST OF THE EAST LINE OF THE SOUTHEAST 1/4 OF SECTION 3, A DISTANCE OF 168.27 FEET TO A POINT IN A LINE 33 FEET SOUTH OF AND PARALLEL WITH THE CENTER LINE OF DUNDEE ROAD, SAID POINT BEING 666.4 FEET WEST OF THE EAST LINE OF SAID SECTION 3, (EXCEPTING FROM SAID PART OF LOT 2 THAT PART THEREOF LYING SOUTH OF A LINE 600 FEET NORTH OF AND PARALLEL WITH THE SOUTH LINE OF SAID LOT 2) ALSO LOT 4, IN MARTIN W. KNITTEL'S SUBDIVISION OF THE NORTH 60 FEET OF LOT 65, LOTS 1 TO 7, LOTS 11 TO 17, OF PETER KNITTEL'S ADDITION TO HUNDERSVILLE, TOGETHER WITH THAT PART OF THE EAST 385.2 FEET OF LOT 3 OF THE SUBDIVISION OF THE KNITTEL FARM LYING NORTH OF THE SOUTH LINE OF TOWN STREET EXTENDED IN SECTIONS 3 AND 10, TOWNSHIP 42 NORTH, RANGE 11 EAST OF THE THIRD PRINCIPAL MERIDIAN, IN COOK COUNTY, ILLINOIS. (EXCEPTING FROM SAID TRACT OF LAND THAT PART THEREOF DEDICATED FOR PUBLIC STREET BY PLAT OF DEDICATION RECORDED MARCH 27, 1996 AS DOCUMENT 96232597).

PARCEL 4:

LOT 1 IN MITCHELL RESUBDIVISION OF THAT PART OF LOT 2 IN OWNER'S DIVISION OF PART OF THE SOUTHEAST 1/4 OF SECTION 3, TOWNSHIP 42 NORTH, RANGE 11 EAST OF THE THIRD PRINCIPAL MERIDIAN AND THAT PART OF LOT 4 IN MARTIN W. KNITTEL'S SUBDIVISION OF PARTS OF SECTIONS 3 AND 10 AFORESAID, ALL IN COOK COUNTY, ILLINOIS, ACCORDING TO THE PLAT THEREOF RECORDED DECEMBER 1, 1992 AS DOCUMENT 92899486.

GRAPHIC SCALE

30' 0 15' 30' 60' 120'

1" = 30'

BASIS OF BEARINGS

THE BASIS OF BEARINGS IS THE STATE PLANE COORDINATE SYSTEM (SPCS) NAD 83 (2007) ZONE 1201 (ILLINOIS EAST) WITH PROJECT ORIGIN AT
LATITUDE: 42-08-18.92412 N
LONGITUDE: 87-55-48.18576 W
ELLIPSOIDAL HEIGHT: 544.108 SFT
GROUND SCALE FACTOR: 1.0000372924
ALL MEASUREMENTS ARE ON THE GROUND.

BENCHMARK

SOURCE: NGS MONUMENT

STATION DESIGNATION: AJ2852
ESTABLISHED BY: SMITH ENGINEERS CONS INC.
DATE: 06-04-2000

ELEVATION: 664.66 (PUBLISHED AND HELD)
DATUM: NAVD88
DESCRIPTION: STATION IS LOCATED IN THE SW CORNER OF INTERSECTION OF IL RT 21 AND LAKE COOK ROAD.



LEGEND

- CABLE TV PEDESTAL
- TRAFFIC LIGHT POLE
- TRAFFIC CONTROL BOX
- TRAFFIC CONTROL VAULT
- TRAFFIC LIGHT
- TELEPHONE PEDESTAL
- TELEPHONE MANHOLE
- PAINTED TELEPHONE LINE
- FIBER OPTIC CABLE LINE
- ANCHOR
- GUY POLE
- UTILITY POLE
- POWER POLE
- LIGHT STANDARD
- ELECTRIC MANHOLE
- ELECTRIC PEDESTAL
- ELECTRIC TRANSFORMER PAD
- ELECTRIC METER
- HANDHOLE
- ELECTRICAL JUNCTION BOX
- ELECTRIC VAULT
- ELECTRIC SERVICE OUTLET BOX
- PAINTED ELECTRIC LINE
- TRANSFORMER PAD
- PAINTED GAS LINE
- GAS VALVE
- GAS METER
- GAS VALVE VAULT
- GAS METER
- PIPELINE MARKER
- MONITORING WELL
- POST INDICATOR VALVE
- WELL HEAD
- FLAGPOLE
- MAILBOX
- SIGN
- POST
- PUBLIC PAY TELEPHONE
- PARKING METER
- WETLAND MARKER
- BASKETBALL HOOP
- AIR CONDITIONER PAD/UNIT
- DECIDUOUS TREE W/ TRUNK SIZE
- NON-DECIDUOUS TREE W/ TRUNK SIZE
- BUSH
- SOIL BORING HOLE W/ NUMBER
- HEADWALL
- CURB INLET
- STORM INLET
- STORM MANHOLE
- FLARED END SECTION
- CLEANOUT
- SANITARY MANHOLE
- HOSE BIB
- B-BOX
- HYDRANT
- WATER VALVE
- WATER VALVE VAULT
- PAINTED WATER LINE
- IRRIGATION HEAD
- IRRIGATION CONTROL VALVE
- WATER METER
- FOUND DISK IN CONCRETE
- FOUND BRASS DISC
- FOUND ROW MARKER
- FIR FOUND IRON ROD
- FRS FOUND RAILROAD SPIKE
- FPK FOUND PK NAIL
- FMG FOUND MAG NAIL
- FCC FOUND CUT CROSS
- FIP FOUND IRON PIPE
- FIB FOUND IRON BAR
- TP SET TRAVERSE POINT
- SPK SET PK NAIL
- SMG SET MAG NAIL
- SIP SET IRON PIPE
- SBM SET CONCRETE MONUMENT WITH BRASS DISC
- SCM SET CONCRETE MONUMENT WITH IRON PIPE

SECTION CORNER — QUARTER SECTION CORNER

- PROPERTY LINE
- EXISTING RIGHT-OF-WAY LINE
- PROPOSED RIGHT-OF-WAY LINE
- EXISTING LOT LINE
- PROPOSED LOT LINE
- EX. & PRO. CENTERLINE
- EXISTING EASEMENT LINE
- PROPOSED EASEMENT LINE
- EX. & PRO. BUILDING SETBACK LINE
- SECTION LINE
- EXISTING FENCELINE (CHAIN LINK)
- EXISTING FENCELINE (WOOD)
- EXISTING FENCELINE (WIRE)
- GUARDRAIL
- RAILROAD TRACKS
- (CATV) UNDERGROUND CABLE TV
- (CATV) UNDERGROUND CABLE TV(ATLAS INFO.)
- (FO) UNDERGROUND FIBER OPTIC CABLE(ATLAS)
- E UNDERGROUND ELECTRIC
- (E) UNDERGROUND ELECTRIC(ATLAS INFO.)
- T UNDERGROUND TELEPHONE
- (T) UNDERGROUND TELEPHONE(ATLAS INFO.)
- G GAS MAIN
- (G) GAS MAIN(ATLAS INFO.)
- W WATER MAIN
- (W) WATER MAIN (ATLAS INFO.)
- (SAN) SANITARY SEWER(ATLAS INFO.)
- (STM) STORM SEWER
- (STM) STORM SEWER(ATLAS INFO.)
- EDGE OF WATER
- OH OVERHEAD WIRES
- CURB
- 700 EXISTING CONTOUR LINE
- ASPHALT PAVING OR WATER (LABELED)
- UNPAVED ROAD
- CONCRETE
- WETLANDS
- EXISTING BUILDING
- MARSH AREA

ABBREVIATIONS

- 782.62 EXISTING TOP OF CURB ELEVATION
- 782.12 EXISTING EDGE OF PAVEMENT ELEVATION
- + 782.62 EXISTING SPOT ELEVATION
- A.P. ACCESSIBLE PARKING
- F.F. FINISHED FLOOR
- T.F. TOP OF FOUNDATION
- CMP CORRUGATED METAL PIPE
- RCP REINFORCED CONCRETE PIPE
- VCP VITRIFIED CLAY PIPE
- FRM. FRAME
- BRK. BRICK
- TC TOP OF CURB
- DEP DEPRESSED CURB
- GUT GUTTER
- EP EDGE OF PAVEMENT
- F.L. FLOW LINE
- CONC. CONCRETE
- BIT. BITUMINOUS
- MH MANHOLE
- CW CONCRETE WALK
- TW TOP OF WALL
- BW BOTTOM OF WALL
- TP TOP OF PIPE
- BW BACK OF WALK
- FES FLARED END SECTION
- INV INVERT
- DIP DUCTILE IRON PIPE
- SD STORM DRAIN
- SAN SANITARY SEWER
- N NORTH
- S SOUTH
- E EAST
- W WEST
- CB CHORD BEARING
- A ARC LENGTH
- R RADIUS
- U.E. UTILITY EASEMENT
- P.U.E. PUBLIC UTILITY EASEMENT
- D.E. DRAINAGE EASEMENT
- M.U.E. MUNICIPAL UTILITY EASEMENT
- I.E. INGRESS & EGRESS EASEMENT
- PC POINT OF CURVATURE
- PCC POINT OF COMPOUND CURVATURE
- PRC POINT OF REVERSE CURVATURE
- PT POINT OF TANGENCY
- (REC) RECORD DATUM
- MEAS. MEASURED DATUM
- [CALC] CALCULATED DATUM
- <DEED> INFORMATION TAKEN FROM DEED
- ETBE EXCEPTION TO BLANKET EASEMENT

GENERAL NOTES

1. COMPARE THIS PLAT, LEGAL DESCRIPTION AND ALL SURVEY POINTS AND MONUMENTS BEFORE ANY CONSTRUCTION, AND IMMEDIATELY REPORT ANY DISCREPANCIES TO SURVEYOR.
2. DO NOT SCALE DIMENSIONS FROM THIS PLAT.
3. THE LOCATION OF THE PROPERTY LINES SHOWN ON THE FACE OF THIS PLAT ARE BASED UPON THE DESCRIPTION AND INFORMATION FURNISHED BY THE CLIENT, TOGETHER WITH THE TITLE COMMITMENT. THE PARCEL WHICH IS DEFINED MAY NOT REFLECT ACTUAL OWNERSHIP, BUT REFLECTS WHAT WAS SURVEYED. FOR OWNERSHIP, CONSULT YOUR TITLE COMPANY.
4. MANHOLES, INLETS AND OTHER UTILITY RIMS OR GRATES SHOWN HEREON ARE FROM FIELD LOCATION OF SUCH, AND ONLY REPRESENT SUCH UTILITY IMPROVEMENTS WHICH ARE VISIBLE FROM ABOVE GROUND AT TIME OF SURVEY, THROUGH A NORMAL SEARCH AND WALK THROUGH OF THE SITE. THE LABELING OF THESE MANHOLES (SANITARY, WATER, ETC.) IS BASED SOLELY ON THE "STAMPED" MARKINGS OF THE RIM. NO UNDERGROUND OBSERVATIONS HAVE BEEN MADE TO VERIFY THE ACTUAL USE OR EXISTENCE OF UNDERGROUND UTILITIES. UNDERGROUND UTILITY LINES SHOWN HEREON, IF ANY, ARE BASED ON FIELD LOCATED STRUCTURES IN COORDINATION WITH ATLAS INFORMATION PROVIDED BY UTILITY COMPANIES THROUGH J.U.L.I.E.'S DESIGN STAGE PROCESS. SEE "UTILITY ATLAS NOTES" HEREON FOR SPECIFICS.
5. NO DRAIN TILES, IF ANY EXIST, SHOWN HEREON.
6. THIS SURVEY MAY NOT REFLECT ALL UTILITIES OR IMPROVEMENTS IF SUCH ITEMS ARE HIDDEN BY LANDSCAPING OR ARE COVERED BY SUCH ITEMS AS DUMPSTERS, TRAILERS, CARS, DIRT, PAVING OR SNOW. AT THE TIME OF THIS SURVEY, SNOW DID NOT COVER THE SITE. LAWN SPRINKLER SYSTEMS, IF ANY, ARE NOT SHOWN ON THIS SURVEY.
7. OTHER THAN VISIBLE OBSERVATIONS NOTED HEREON, THIS SURVEY MAKES NO STATEMENT REGARDING THE ACTUAL PRESENCE OR ABSENCE OF ANY SERVICE.
8. CALL J.U.L.I.E. AT 1-800-892-0123 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO ANY DIGGING OR CONSTRUCTION.
9. PUBLIC AND/OR PRIVATE RECORDS HAVE NOT BEEN SEARCHED TO PROVIDE ADDITIONAL INFORMATION. OVERHEAD WIRES AND POLES (IF ANY EXIST) ARE SHOWN HEREON, HOWEVER THEIR FUNCTION AND DIMENSIONS HAVE NOT BEEN SHOWN.
10. THIS IS NOT A TOPOGRAPHIC SURVEY AND IS NOT TO BE USED FOR DETAILED CIVIL DESIGN WORK.
11. A CURRENT CHICAGO TITLE INSURANCE COMPANY'S TITLE COMMITMENT NO. 21GST187026RM DATED FEBRUARY 11, 2021 WAS PROVIDED FOR SURVEYOR'S USE AT THE TIME OF PREPARATION OF THIS SURVEY. SEE "NOTES FROM SCHEDULE B, PART II" SHOWN HEREON FOR DETAILS.

THE SURVEYOR WAS NOT PROVIDED MANY OF THE OLD TORRENS "LR" DOCUMENTS FOR REVIEW. THE SURVEYOR RELIED UPON MANY SUPPORTING DOCUMENTS SUCH AS, I.D.O.T. PLAT OF HIGHWAYS, SIDWELLS, SURVEYS-BY-OTHERS, IN ORDER TO COMPLETE THE BOUNDARY SURVEY OF THE PROPERTY. THE SURVEY MAY NEED TO BE UPDATED UPON REVIEW OF SUBSEQUENT FORTHCOMING DOCUMENTATION.

UTILITY ATLAS NOTES:

J.U.L.I.E. DESIGN STAGE REQUEST
DIG NUMBER A0571471 RECEIVED 02/26/21 .

CONTACTS PROVIDED BY J.U.L.I.E. & LISTED BELOW WERE CONTACTED BY V3 VIA FAX, REQUESTING UTILITY ATLAS INFORMATION ON 02/26/21.

CONTACTS	RESPONSE
A. T. & T. DISTRIBUTION	NO RESPONSE
COM-ED	RESPONDED WITH ATLAS
VILLAGE OF WHEELING	RESPONDED WITH ATLAS
COMCAST	NO RESPONSE
NICOR GAS	RESPONDED WITH ATLAS
NORTH SHORE GAS COMPANY	NO RESPONSE
WINDSTREAM KDL/MCLEOD USA	RESPONDED "ALL CLEAR"
A. T. & T. / T-TCG	NO RESPONSE
LEVEL 3 (CENTURYLINK)	RESPONDED WITH ATLAS
NORTHWEST WTR. COMM	NO RESPONSE
VINAKOM COMMUNICATIONS	RESPONDED WITH ATLAS
WEST SHORE PIPE LINE	RESPONDED "NO CONFLICT"

NOTES FROM SCHEDULE B PART II

(SEE GENERAL NOTES #11)

	EXCEPTIONS	NOTE
AZ	PLAT OF EASEMENT NO. 3234099	(j)
AY	PUBLIC UTILITY EASEMENT; DOC. T2988288	(j)
AS	RIGHTS OF THE PUBLIC UTILITIES	(i)
AT	ENCHROACHMENT	(i)
AU	ENCHROACHMENT	(i)
AW	EASEMENT DOC. 96551984	(e)
AN	PLAT OF DEDICATION DOC. LR3234108	(a)
AQ	BUILDING LINES, DOC. 92899486	(a)
AR	PLAT OF SUBDIVISION, DOC. 92899486	(a)
AK	PLAT OF HIGHWAYS, DOC. 1913716019 & 2005216113	(a)

EXCEPTIONS NOT SHOWN ABOVE AFFECT THE PROPERTY BUT ARE NOT PLOTTABLE.
CLARIFICATION STATEMENTS

a. its location is shown;
b. its location cannot be determined from the record document;
c. there was no observed evidence at the time of the fieldwork;
d. it is a blanket easement;
e. it is not on, does not touch, and/or - based on the description contained in the record document - does not affect, the surveyed property;
f. it limits access to an otherwise abutting right of way;
g. the documents are illegible; or
h. the surveyor has information indicating that it may have been released or otherwise terminated
i. see current survey shown hereon
j. document not provided for Surveyor's review

SURVEYOR'S CERTIFICATE

STATE OF ILLINOIS)
)SS
COUNTY OF DUPAGE)

TO: INTREPID PROPERTIES, INC.
CII WHEELING, LLC, AN ILLINOIS LIMITED LIABILITY COMPANY, AS TO PARCELS 1, 3 AND 4
CII 33 S. WHEELING, LLC, AN ILLINOIS LIMITED LIABILITY COMPANY, AS TO PARCEL 2
CHICAGO TITLE INSURANCE COMPANY

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2016 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 2, 3, 4, 5, 8 AND 11(A) OF TABLE A THEREOF.

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR BOUNDARY SURVEYS.

THE FIELD WORK WAS COMPLETED ON MARCH 9, 2021.

DATED THIS 17TH DAY OF MARCH, A.D., 2021.

CHARLES W. BARTOSZ
ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-3188
MY LICENSE EXPIRES ON NOVEMBER 30, 2022.
V3 COMPANIES, LTD. PROFESSIONAL DESIGN FIRM NO. 184000902
THIS DESIGN FIRM NUMBER EXPIRES APRIL 30, 2021.
CBARTOSZ@V3CO.COM

CHARLES W. BARTOSZ 3188 PROFESSIONAL LAND SURVEYOR STATE OF ILLINOIS WOODRIDGE, ILLINOIS

Engineers
Scientists
Surveyors

7325 Janes Avenue, Suite 100
Woodridge, IL 60517
630.724.9200 voice
630.724.0384 fax
v3co.com

PREPARED FOR:
Intrepid Properties, Inc.
2311 W. 22nd Street, Suite #208
Oak Brook, IL 60523
630.575.8338

REVISIONS

NO.	DATE	DESCRIPTION

ALTA/NSPS LAND TITLE SURVEY
Carollo - Wheeling IL

Project No: 210127
Group No: VP01.1

DRAFTING COMPLETED: 03-17-21 | DRAWN BY: SPK | PROJECT MANAGER: CWB
FIELD WORK COMPLETED: 03-09-21 | CHECKED BY: CWB | SCALE: 1" = 30'

SHEET NO. 1 of 1

N:\2021\210127\Drawings\ACAD\SVY\VP01.1\ALT210127_20210309.dwg, 3/18/2021 3:03:38 PM