


MAINE METAL BUILDING INC.

MIKE SULLIVAN STORAGE BUILDING

FO# 22636

Building 1 of 1



INDEX OF DRAWINGS

Page	Drawing Title	REV NO.
	Cover Page	0
1	Specifications	0
2	Anchor Bolt Plan	0
3	Rigid Frame Reactions	0
4	EndWall Reactions, Design Criteria	0
5	Anchor Bolt Details	0
6	Roof Framing	0
7	Roof Panel Layout	0
8	Rigid Frame #1	0
9	Rigid Frame #2	0
10	Rigid Frame #3	0

Page	Drawing Title	REV NO.
11	Front Sidewall Framing	0
12	Back Sidewall Framing	0
13	Left Endwall Framing	0
14	Right Endwall Framing	0
15	Detail Page #1	0
16	Detail Page #2	0
17	Detail Page #3	0
18	Detail Page #4	0
19		0
20		0
21		0

Page	Drawing Title	REV NO.
22		0
23		0
24		0
25		0
26		0
27		0
28		0
29		0
30		0
31		0
32		0

GENERAL
All materials included in the Metal Building System are in accordance with the manufacturer's standard materials and details unless otherwise specified on the order documents. (MBMA 2012 Metal Building Systems Manual, Part IV, Section 2.1)

DESIGN RESPONSIBILITY
The manufacturer is responsible only for the structural design of the Metal Building System it sells to the purchaser / customer. Neither the manufacturer nor the manufacturer's engineer is the design professional or engineer of record for the construction project. The manufacturer is not responsible for the design of any component or materials not sold by it, or their interface and connection with Metal Building System unless such design responsibility is specifically required by the order documents. (MBMA 2012 Metal Building Systems Manual, Part IV, Section 3.1)

FOUNDATION DESIGN AND ANCHOR BOLTS
The manufacturer is not responsible for the design, materials, and workmanship of the foundation. The anchor bolt plans prepared by the manufacturer are intended to show only the anchor bolt location, diameter (based on ASTM A36 bolts), and quantity required to connect the Metal Building System to the foundation. (MBMA 2012 Metal Building Systems Manual, Part IV, Section 3.2.2).
It is the responsibility of the end customer to ensure that adequate provisions are made for specifying bolt embedment, bearing angles, tie rods, and / or associated items embedded in the concrete foundation, as well as foundation design based on the loads imposed by the Metal Building System, or other imposed loads, and the bearing capacity of the soil and other conditions of the building site. (MBMA 2012 Metal Building Systems Manual, Part IV, Section 3.2.2)
U.S. - Anchor bolts shall be accurately set to a tolerance of +/- 1/8 in both elevation and location (AISC Code of Standard Practice for Steel Buildings and Bridges).
Canada - Anchor bolts shall be accurately set in accordance with CISC Code of Standard Practice, June 2008, Clause 7.7.1

ADJACENT EXISTING BUILDINGS
The manufacturer does not investigate the influence of the Metal Building System on adjacent existing buildings or structures. The end customer assures that such buildings and structures are adequate to resist snow loads or other conditions as a result of the presence of the Metal Building System. (MBMA 2012 Metal Building Systems Manual, Part IV, Section 3.2.5)

SHOP-PRIMED STEEL
All structural members of the Metal Building System not fabricated of corrosion resistant material or protected by corrosion resistant coating are painted with one coat of shop primer. All surfaces to receive shop primer are cleaned of loose rust, loose mill scale and other foreign matter by using, as a minimum the hand tool cleaning method SSPC-SP2 (Steel Manual, Structures Painting Council) prior to painting. The coat of shop primer is intended to protect the steel framing for only a short period of exposure to ordinary atmospheric conditions. Shop-primed steel should be placed on blocking to prevent contact with the ground, and so positioned as to minimize water holding pockets, dust, mud or other contamination of the primer film. Repairs of damage to primed surfaces and or removal of foreign material due to improper field storage or site conditions are not the responsibility of the manufacturer. (CISC Code of Standard Practice, June 2008, Clause 6.8; (MBMA 2012 Metal Building Systems Manual, Part IV, Section 4.2.4).

ERECTION-GENERAL
The erector, by entering into contract to erect the building, holds itself out as skilled in the erection of Metal Building Systems and is responsible for complying with all applicable local, federal, and state construction and safety regulations including OSHA regulations as well as any applicable requirements of local, national, or international union rules or practices. (CISC Code of Standard Practice, June 2008, Clause 7.2; (MBMA 2012 Metal Building System Manual, Part IV, Section 6.9).

The erector shall erect the Metal Building System in accordance with the erection drawings, the Erection and Detail Manual (February 2012), and / or the Seam-Lok Technical - Erection manual (May 2012) as furnished by the manufacturer. The aforementioned erection information is intended to illustrate the layout of the framing members, provide the associated connection details, and suggests sequence of erection. It is not intended to specify any particular method of erection to be followed by the erector. The erector remains solely responsible for the safety and appropriateness of all techniques and methods utilized by its crews in the erection of the Metal Building System. The erector is responsible for supplying any safety devices such as scaffolds, runways, nets, et, which may be required to safely erect the Metal Building System. (MBMA 2012 Metal Building Systems Manual, Part IV, Section 6.9) The manufacturer expressly disclaims any responsibility for injury to persons in the course of erection or for damages to the product itself. Field erection of a Pre-Engineered Metal Building, as in all construction projects, involves hazards to persons within the area of the construction and risk of damage to the property itself. Only experienced persons who are skilled and qualified in the erection of Metal Building Systems should be permitted to field-erect a building due to the hazards of this construction activity. The manufacturer is not responsible for the erection of the Metal Building System, the supply of any tools or equipment, or any other field work. The manufacturer provides no field supervision for the erection of the structure nor does the manufacturer perform any intermediate or final inspections of the Metal Building System during or after erection.

The erector shall furnish temporary guys and bracing where needed for squaring, plumbing, and securing the structural framing against loads, such as wind loads acting on the exposed framing as well as loads due to erection equipment and erection operation, but not including loads resulting from the performance of work by others. Bracing furnished by the manufacturer for the Metal Building System cannot be assumed to be adequate during erection. Temporary supports such as temporary guys, braces, false work, cribbing, or other elements required for the erection operation will be determined, erected, and installed by the erector. (AISC Code of Standard Practice for Steel Buildings and Bridges, April 14, 2010, Section 7.10.3; CISC Code of Standard Practices, June, 2008, Clause 1.5; MBMA 2012 Metal Buildings System Manual, Part IV, Section 6.2.1.5).

ERECTION TOLERANCES
U.S. ; Erection tolerances are those set forth in AISC code of standard practice except individual members are considered, plumb, level and aligned if the deviation does not exceed 1:500. (AISC Code of Standard Practice for Steel Buildings and Bridges April 14, 2010 Section 7.13.1; MBMA 2012 Metal Building Systems Manual, Part IV, Section 6.8)
Canada; Erection tolerances are those set forth in CISC Code of Standard Practice except individual members are considered plumb, level and aligned if the deviation does not exceed 1:500. (CISC Handbook of Steel Construction, Tenth Edition, Second Revised Printing, Part 1, Clause 29.3; MBMA 2012 Metal Building Systems Manual, Part IV, Section 6.8)

BOLT TIGHTENING
The proper tightening and inspection of all fasteners is the responsibility of the erector (Reference RCSC for structural joints using high strength bolts; August 1, 2014). All high strength (ASTM F3125, A325, A490) bolts and nuts must be tightened by the "turn-of-the-nut" method unless otherwise specified by the end customer in the contract documents. Inspection of high strength bolt and nut installation by other than the erector must also be specified in the contract documents and the erector is responsible for ensuring that the installation procedures are compatible prior to the start of erection (CISC Handbook of Steel Construction, Tenth Edition, Second Revised Printing, Part 1, Clause 23.8.2), (MBMA 2012 Metal Building Systems Manual, Part IV, Section 6.9).

MATERIALS	ASTM DESIGNATION	MINIMUM YIELD	MATERIALS	ASTM DESIGNATION	MINIMUM YIELD
Hot-Rolled Mill Sections	A 36, A 572, A 992	Fy = 36 ksi and/or 50 ksi	Roof and Wall Sheeting	A 792, Gr. 50 Class 1 A 792, Gr. 80	Fy = 50 ksi Fy = 80 ksi
Structural Steel Plates	A 572, A 1011	Fy = 55 ksi	Mild Steel Bolts	A 307	Fy = 36 ksi
Structural Steel Bars	A 572 or A 529	Fy = 55 ksi	High Strength Bolts	F3125: A 325-N A 490-N	Fy = 92 or 81 ksi N/A
Cold Formed Light Gauge Shapes	A 653 Gr. 55	Fy = 55 ksi	Anchor Rods (If supplied)	A 36	Fy = 36 ksi
Cable Bracing	A 475, EHS	N/A	Pipe and Hollow Structural Sections	A 500 Gr. B	Fy = 42 ksi, 46 ksi
Rod Bracing	A 36	Fy = 36 ksi			

CORRECTION OF ERRORS AND REPAIRS
The correction of minor misfits by the use of drift pins to draw the components into line, shimming, moderate amounts of reaming, chipping, and cutting, and the replacement of minor shortages of material are a normal part of erection and are not subject to claim. (AISC Code of Standard Practice for Steel Buildings and Bridges, April 14, 2010, Section 7.14; CISC Code of Standard Practice, June 2008, Clause 7.15; MBMA 2012 Metal Building Systems Manual, Part IV, Section 6.10).

DRAWING DISCREPANCIES
In case of discrepancies between the manufacturers steel plans and plans for other trades, the manufacturers steel plans govern. (AISC Code of Standard Practice for Steel Buildings and Bridges, April 14, 2010, Section 3.3; CISC Code of Standard Practice, June 2008, Clause 3.4; MBMA 2012 Metal Building Systems Manual, Part IV, Section 3.1).

DELIVERIES
Delivery of any material by the manufacturers carrier, a common carrier, or to purchasers/ customers own leased, chartered, or authorized conveyance shall constitute delivery to builder, and thereafter, such material shall be at builders risk. If builder chooses to use its own, or private carrier, it shall be solely responsible for compliance with all applicable government regulations. All charges shall be borne by the builder. The manufacturers responsibility for damage or loss ceases upon delivery of shipment to carrier. The manufacturer will endeavor to deliver on the required date. The manufacturers truck is not considered as being late if deliveries are between 8am - 12pm (morning) and 12pm - 5pm (afternoon). However, the manufacturer cannot be held responsible for circumstances beyond our control. For deliveries via the manufacturers truck, the manufacturer will only honor claims that were approved by the customer service department at the time of delivery. For deliveries via contract carriers, it is the responsibility of the customer to file claims with the carrier. The manufacturer cannot assume any liability for the claim.

SHORTAGES
The purchaser /customer should make an inspection upon arrival of all building components. The purchaser/customer must note on the freight bill any missing item(s) and notify the manufacturers customer service department immediately; otherwise, the manufacturer cannot be held responsible for any shortages. If any item is damaged, note on the bill of lading and file a claim with the freight agent. Concealed shortages must be reported to the manufacturers customer service department within the following time frames (date from receipt of first delivery), based on the project shipment size, i.e., number of truck loads used in delivery.
1 to 3 loads_2 weeks 4 loads and over_3 weeks The manufacturers responsibility for shortages expires at the end of these time periods.


FABRICATION ERRORS
The purchaser/customer is responsible for contacting the customer service department to advise the manufacturer of fabrication problems and corresponding cost estimates. The manufacturer will be responsible for providing the builder with verbal approval to proceed with appropriate field corrections. This will be done in a timely manner. IF THE BUILDER PROCEEDS WITH CORRECTIVE WORK WITHOUT THE MANUFACTURERS APPROVAL, HE DOES SO AT HIS OWN RISK. The manufacturer shall not be responsible for any claims where the purchaser/customer has not documented the problem, its correction, and reasonable costs for repair, and submitted this documentation for payment within 30 days of the occurrence.

INVOICE PAYMENT
By acceptance of the materials of services set forth in the invoice, the purchaser/customer agrees to pay the invoice amount within the time period specified on the invoice. AT NO TIME IS IT ACCEPTABLE TO DEDUCT A BACK CHARGE OR SHORTAGE FROM AN INVOICE.

SAFETY PROCEDURES
The manufacturer is committed to manufacturing a quality product that can be erected safely. Although good job site practices and a commitment to safety by the erector are beyond the control of the manufacturer, the manufacturer highly recommends the erector provide good, safe working conditions on the job site. The erector should follow all local, state, and federal health and safety regulations at all times. Accident prevention practices should be implemented and each employee should know emergency procedures. The manufacturer also recommends daily meetings to discuss erection safety procedures. For additional information concerning federal health and safety regulations, contact the occupational safety and health administration (osha).

U.S. Department of Labor
Occupational Safety and Health Administration
200 Constitution Avenue, N.W.
Washington, DC 20210
www.osha.gov

The manufacturer shall not be responsible for personal injury or property damage as a result of failure to follow all applicable safety regulations and material handling and installation recommendations.



CORLE
CORLE BUILDING SYSTEMS
404 Sarah Furnace Road - Imbler, PA 16655 (814) 276 - 9811

MIKE SULLIVAN STORAGE BUILDING
40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0
ENG: IRM DWN: BJC APPD: IRM

F.O.22636

REV.	DESCRIPTION	DATE


MIKE SULLIVAN STORAGE BUILDING

DRAWING STATUS



FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.



STATE OF MAINE
T. JAMES EISENMAN, JR.
No. 9637
LICENSED PROFESSIONAL ENGINEER



ANCHOR BOLT PLAN
 NOTE: All Base Plates @ 100'-0" (U.N.)
 Finished Floor @ 100'-0"

404 Sarah Furnace Road - Imler, PA 19655 (814) 276 - 9811

MIKE SULLIVAN STORAGE BUILDING
 40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0
 ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

DRAWING STATUS	
REV.	DESCRIPTION

<p>FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.</p>	<p>FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.</p>	<p>FOR CONSTRUCTION: FINAL DRAWINGS.</p>
---	---	---


STATE OF MAINE

T. JAMES EISENMAN, JR.
 No. 9637

LICENSED PROFESSIONAL ENGINEER

3/26/19

FRAME LINES: 1 2 3 4



RIGID FRAME: BASIC COLUMN REACTIONS (k)

Frame Line	Column Line	Dead		Collateral		Live		Snow		Wind_Left1		Wind_Right1	
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert
1	E	0.2	1.1	0.5	1.8	0.8	3.3	1.7	7.5	-0.3	-1.9	-0.3	-1.9
1	A	-0.2	1.1	-0.5	1.8	-0.8	3.3	-1.7	7.5	0.3	-1.9	0.3	-1.9
2	E	0.3	1.6	1.0	3.5	1.7	6.4	3.0	12.7	-2.8	-3.7	2.4	-1.5
2	A	-0.3	1.6	-1.0	3.5	-1.7	6.4	-3.0	12.7	-2.4	-3.7	2.8	-3.7
3*	E	0.4	2.0	1.5	4.8	2.4	8.8	4.1	16.8	-4.9	-4.9	4.8	-0.7
3*	A	-0.4	2.0	-1.5	4.8	-2.4	8.8	-4.1	16.8	-4.8	-0.7	4.9	-4.9

Frame Line	Column Line	Wind_Left2		Wind_Right2		Wind_Long1		Wind_Long2		Seismic_Left		Seismic_Right	
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert
1	E	-1.0	-2.1	0.4	-1.6	-0.7	-3.2	0.3	1.4	-0.3	-0.2	0.3	0.2
1	A	-0.4	-1.6	1.0	-2.1	0.7	-3.2	-0.3	1.4	-0.3	0.2	0.3	-0.2
2	E	-3.4	-2.3	2.1	0.1	0.6	-4.7	-0.2	-5.1	-0.5	-0.4	0.5	0.4
2	A	-2.1	0.1	3.4	-2.3	0.2	-5.1	-0.6	-4.7	-0.5	0.4	0.5	-0.4
3*	E	-5.8	-1.9	3.9	2.3	2.3	-8.0	0.5	-8.7	-0.7	-0.6	0.7	0.6
3*	A	-3.9	2.3	5.8	-1.9	-0.5	-8.7	-2.3	-8.0	-0.7	0.6	0.7	-0.6

Frame Line	Column Line	Seismic_Long	
		Horiz	Vert
1	E	0.0	0.0
1	A	0.0	0.0
2	E	0.0	0.0
2	A	0.0	0.0
3*	E	0.0	-1.6
3*	A	0.0	-1.6

3* Frame lines: 3 4

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Bolt Qty	Anc. Bolt Dia	Base Plate (in)			Grout (in)
				Width	Length	Thick	
1	E	4	0.750	8.000	11.50	0.500	0.0
1	A	4	0.750	8.000	11.50	0.500	0.0

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Bolt Qty	Anc. Bolt Dia	Base Plate (in)			Grout (in)
				Width	Length	Thick	
2	E	4	0.750	8.000	11.50	0.500	0.0
2	A	4	0.750	8.000	11.50	0.500	0.0

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Bolt Qty	Anc. Bolt Dia	Base Plate (in)			Grout (in)
				Width	Length	Thick	
3*	E	4	0.750	8.000	11.50	0.500	0.0
3*	A	4	0.750	8.000	11.50	0.500	0.0

3* Frame lines: 3 4

404 Sarah Furnace Road - Imier, PA 16655 (814) 276-9611

MIKE SULLIVAN STORAGE BUILDING

40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0

ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

MIKE SULLIVAN STORAGE BUILDING


REV.	DESCRIPTION	DATE

DRAWING STATUS

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: FINAL DRAWINGS.



ENDWALL COLUMN:				BASIC COLUMN REACTIONS (k)											
Frm Line	Col Line	Dead Vert	Wind Press	Wind Suct	Wind Suct	Wind Suct	Wind Suct	Wind Suct	Wind Suct	Wind Suct	Wind Suct	Wind Suct	Wind Suct	Wind Suct	Wind Suct
2	D	0.3	-3.0	3.3											
2	B	0.3	-3.0	3.3											

Frm Line	Col Line	Dead Vert	Collat Vert	Live Vert	Snow Vert	Wind_Left1 Horz	Wind_Left1 Vert	Wind_Right1 Horz	Wind_Right1 Vert	Wind_Left2 Horz	Wind_Left2 Vert	Wind_Right2 Horz	Wind_Right2 Vert	Wind Press Horz
5	A	0.7	1.2	2.5	5.3	4.5	-6.9	0.0	4.9	4.5	-5.4	0.0	6.3	-1.1
5	C	1.6	3.7	6.0	10.3	0.0	6.4	4.5	-9.5	0.0	7.2	4.5	-8.7	-6.6
5	E	0.7	1.2	2.5	5.3	0.0	-4.6	0.0	-0.5	0.0	-3.1	0.0	1.0	-1.1

Frm Line	Col Line	Wind Suct Horz	Wind_Long1 Horz	Wind_Long1 Vert	Wind_Long2 Horz	Wind_Long2 Vert	Seis_Left Horz	Seis_Left Vert	Seis_Right Horz	Seis_Right Vert	E2PAT_SL_1- Horz	E2PAT_SL_1- Vert	E2PAT_SL_2- Horz	E2PAT_SL_2- Vert
5	A	1.3	0.0	0.0	1.7	-4.1	0.6	-0.8	0.0	1.2	0.0	2.0	0.0	-0.3
5	C	7.3	1.7	-7.7	0.0	-1.8	0.0	0.9	0.6	-1.3	0.0	2.7	0.0	2.7
5	E	1.3	0.0	-1.7	0.0	-3.5	0.0	-0.1	0.0	0.1	0.0	-0.3	0.0	2.0

ANCHOR BOLT SUMMARY

Qty	Locate	Dia (in)	Type
⊕ 20	Endwall	3/4"	
⊕ 32	Frame	3/4"	

BUILDING BRACING REACTIONS

Loc	Wall Line	Col Line	Reactions in plane of wall ± Reactions(k)				Panel Shear (lb/ft)	Note
			Wind Horz	Wind Vert	Seismic Horz	Seismic Vert		
L_EW	1						(h)	
F_SW	A	3,4	3.5	*	1.9	*		
R_EW	5	A,C	Bracing, see EW reactions					
B_SW	E	4,3	3.5	*	1.9	*		

(h) Rigid frame at endwall

*See RF reactions table for vertical and horizontal reactions in plane of the rigid frame.

ENDWALL COLUMN:		ANCHOR BOLTS & BASE PLATES					
Frm Line	Col Line	Anc. Bolt Qty	Anc. Bolt Dia	Base Plate Width	Base Plate Length	Base Plate Thick	Grout (in)
2	D	4	0.750	6.000	9.875	0.375	0.0
2	B	4	0.750	6.000	9.875	0.375	0.0
5	A	4	0.750	6.000	7.875	0.375	0.0
5	C	4	0.750	6.000	8.125	0.375	0.0
5	E	4	0.750	6.000	7.875	0.375	0.0

DESIGN INFORMATION

- All loading conditions are examined and only the maximum / minimum H or V and the corresponding H or V are reported.
- Positive reactions are shown in the sketch. Foundation loads are in opposite directions.
- Bracing reactions are in the plane of the brace with the H pointing away from the braced bay. The vertical reaction is downward.
- Building reactions are based on the following building data:

DESIGN CRITERIA	SEISMIC CRITERIA	DEFLECTION LIMITS
Width (ft) = 40	Seismic Importance = 1.00	ENDWALL COLUMN L/120
Length (ft) = 70	Occupancy Category = II - Normal	ENDWALL RAFTER (Live) L/180
Eave Height (ft) = 16		ENDWALL RAFTER (Wind) L/180
Roof Slope (rise/12) = 8:0.12	Mapped Spectral Response Accelerations	WALL GIRTS L/90
Building Code = IBC 15	Ss = 0.2200	PURLIN (LIVE) L/180
Local Code (State/Prov) = IBC 15	S1 = 0.0750	PURLIN (WIND) L/150
Dead Load (psf) = 2.250	---Spectral Response Coefficients---	WALL PANEL L/90
Collateral Load (psf) = 10.00	Sds = 0.2347	ROOF PANEL (Live) L/180
Roof Live Load (psf) = 20.00	Sd1 = 0.1200	ROOF PANEL (Wind) L/120
Frame Live Load (psf) = 20.00	Site Class = D	Main Frame (Horiz) L/60
	Seismic Design Category = B	Main Frame (Vert) L/180
	---Base Shear---	WIND BRACING L/60
Snow: Ground Snow Load (psf) = 50.00	Expanded Formula = 0.667*le*Fa*Ss*W/R	Main Frame (Crane) L/100
Snow Importance = 1.00	Longitudinal Base Shear = 3.71	Main Frame (Seismic) L/50
Thermal Coefficient = 1.00	Transverse Base Shear = 4.86	SEISMIC BRACING L/50
Snow Exposure Factor = 1.0000	---Seismic Response Coefficients---	PARTITION COLUMN L/120
Slippery Roof = N	Frame = 0.067	PARTITION GIRT L/120
Roof Snow Load (psf) = 35	FSW = 0.047	PARTITION PANEL L/120
Wind: Ultimate Wind Speed (mph) = 117 mph	BSW = 0.047	
Occupancy Category = II - Normal	---Response Modification Factors---	
Importance - Wind = 1.00	Frame = 3.5	
Wind Exposure = B	FSW = 5	
Enclosure Classification = C	BSW = 5	
---Internal Pressure Coefficients---		
Pressure = 0.18		
Suction = -0.18		
---Components & Cladding---		
Design Pressure: Pressure (psf) = 24.60		
Suction (psf) = -32.88		
Equivalent Lateral Brace Force Procedure.		

404 Sarah Furnace Road - Imler, PA 16655 (814) 276 - 9611

MIKE SULLIVAN STORAGE BUILDING

40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0

ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

MIKE SULLIVAN STORAGE BUILDING

DRAWING STATUS


REVISION HISTORY






REV.	DESCRIPTION	DATE

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: FINAL DRAWINGS.





ADDITIONAL LOADING INFORMATION

Mezzanine Loads:

Dead Load _____ PSF

Collateral Load _____ PSF

Live Load _____ PSF

Crane Information:

Crane Type _____

CMAA Service Class _____

Crane capacity = _____ Kips

Bridge Weight = _____ Kips

Hoist/Trolley Weight = _____ Kips

Wheel Spacing = _____ Ft.

Additional Loads:

1. _____

2. _____

3. _____

404 Sarah Furnace Road - Imler, PA 16655 (814) 276 - 9811

MIKE SULLIVAN STORAGE BUILDING

40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0

ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

DRAWING STATUS		REVISION HISTORY	
REV.	DESCRIPTION	DATE	

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR CONSTRUCTION: FINAL DRAWINGS.

MIKE SULLIVAN STORAGE BUILDING

T. JAMES EISENMAN, JR.
No. 9637
LICENSED PROFESSIONAL ENGINEER




3/26/19

PAGE 5 OF 18



(4) 26'-4 1/2"

(4) 26'-4 1/2"



GENERAL NOTES:
 Panel "Start" and "End" dimensions must be followed for the proper installation of the gable trim(s) provided.

ROOF SHEETING PLAN
 PANELS: 24 Ga. L4 - TBD
 [A] SOFFIT PANELS: 26 Ga. R - TBD

CORLE ENGINEERING
 404 Sarah Furnace Road - Imlier, PA 16655 (814) 276 - 9811

MIKE SULLIVAN STORAGE BUILDING
 40'-0" x 70'-0" x 16'-0"
 DATE: 3/13/19 REVISION: 0
 ENG: IRM DWN: BJC APPD: IRM

F.O. 22636


DRAWING STATUS	
REV.	DESCRIPTION

MIKE SULLIVAN STORAGE BUILDING

FOR APPROVAL:
 THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT:
 THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR CONSTRUCTION:
 FINAL DRAWINGS.



SPLICE BOLT TABLE


Mark	Qty		Int	Type	Dia	Length
	Top	Bot				
SP-1	4	4	2	A325	0.750	2.00
SP-2	4	4	0	A325	0.500	1.50

▽ FLANGE BRACES: Both Sides(U.N.)
 FB_{xx}B(1)
 B - L20X3/16
 A - L15X1/8



MEMBER TABLE

Mark	Web Depth		Web Thick	Plate Length	Outside Flange			Inside Flange		
	Start	End			W	Thk	Length	W	Thk	Length
RF2-1	11.0	12.7	0.149	60.0	6	1/4"	186.9	6	1/4"	174.8
RF2-2	12.7	16.0	0.219	130.7	6	1/4"	16.2	6	1/4"	263.8
RF2-3	16.0	11.2	0.149	210.6	6	1/4"	270.6	6	1/4"	263.8
RF2-4	11.2	10.0	0.149	60.0	6	1/4"	270.6	6	1/4"	263.8
RF2-5	10.0	11.2	0.149	60.0	6	1/4"	16.2	6	1/4"	174.8
RF2-6	11.2	16.0	0.149	210.6	6	1/4"	16.2	6	1/4"	174.8
RF2-7	16.0	12.7	0.219	130.7	6	1/4"	186.9	6	1/4"	186.9
RF2-8	12.7	11.0	0.149	60.0	6	1/4"	186.9	6	1/4"	186.9



BUILDING CROSS SECTION: FRAME LINE 2

GENERAL NOTES:

- See Detail Sheets for Connection Information.
- See Shipping List for Flange Brace Lengths.

CORLE ENGINEERING
 404 Sarah Furnace Road - Imber, PA 16655 (814) 276 - 9611

MIKE SULLIVAN STORAGE BUILDING
 40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0
 ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

MIKE SULLIVAN STORAGE BUILDING

REV.	DESCRIPTION	DATE

DRAWING STATUS

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR CONSTRUCTION: FINAL DRAWINGS.

T. JAMES EISENMAN, JR.
 No. 9637
 LICENSED PROFESSIONAL ENGINEER


3/26/19

SPLICE BOLT TABLE						
Mark	Qty		Int	Type	Dia	Length
	Top	Bot				
SP-1	4	4	2	A325	0.750	2.25
SP-2	4	4	0	A325	0.500	1.50

▽ FLANGE BRACES: Both Sides(U.N.)
 FBxxA(1)
 A - L15X1/8
 B - L20X3/16



MEMBER TABLE								
Mark	Web Depth		Web Thick	Plate Length	Outside Flange		Inside Flange	
	Start/End				W x Thk x Length	W x Thk x Length		
RF3-1	11.0/14.4		0.149	60.0	6 x 1/4" x 186.9	6 x 1/4" x 175.9		
	14.4/21.0		0.188	133.3	6 x 1/4" x 20.9			
RF3-2	18.0/10.0		0.149	265.7	6 x 1/4" x 265.7	6 x 5/16" x 145.8		
					6 x 1/4" x 113.2			



GENERAL NOTES:
 1. See Detail Sheets for Connection Information.
 2. See Shipping List for Flange Brace Lengths.

404 Sarah Furnace Road - Imbler, PA 16665 (814) 276-9811
MIKE SULLIVAN STORAGE BUILDING
 40'-0" x 70'-0" x 16'-0"
 DATE: 3/13/19 REVISION: 0
 ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

REV.	DESCRIPTION	DATE

MIKE SULLIVAN STORAGE BUILDING

DRAWING STATUS

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FINAL DRAWINGS.

STATE OF MAINE
 T. JAMES EISENMAN, JR.
 No. 9637
 LICENSED PROFESSIONAL ENGINEER
 3/26/19
PAGE 10 OF 18

MEMBER TABLE			
FRAME LINE A			
QUAN	MARK	PART	LENGTH
4	G-15	8X25Z16	22'-3 1/2"
2	G-16	8X25Z16	21'-1 1/2"
2	CB-3	CABLE250	22'-9 9/16"



SIDEWALL FRAMING: FRAME LINE A



SIDEWALL SHEETING & TRIM: FRAME LINE A

PANELS: 24 Ga. R - TBD

GENERAL NOTES:

1. Use TEK5WW screws in place of SD150 panel screws at all 10 gage members.
2. All connections to door or window jambs where the clip is not designated in the clip table / drawing are made with JC# clips (#= Girt Depth).

TRIM COLORS	
EAVE TRIM = TBD	CORNER TRIM = TBD
BASE TRIM = TBD	GUTTER =
DOOR TRIM = TBD	DOWNSPOUTS =
RAKE TRIM = TBD	
* LINER TRIM = Liner panel color	
* SOFFIT TRIM = Soffit panel color	
* ONLY APPLICABLE IF LINER TRIM OR SOFFIT PANEL IS INDICATED ON BUILDING ORDER.	

CORLE
 BUILDING SYSTEMS
 404 Sarah Furnace Road - Imbler, PA 16655 (814) 276 - 9611

MIKE SULLIVAN STORAGE BUILDING

40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0
 ENG: IRM DWN: BJC APPD: IRM

F.O. 22636


MIKE SULLIVAN STORAGE BUILDING

DRAWING STATUS


FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR CONSTRUCTION: FINAL DRAWINGS.



MEMBER TABLE			
FRAME LINE E			
QUAN	MARK	PART	LENGTH
4	G-15	8X25Z16	22'-3 1/2"
2	G-17	8X25Z16	21'-1 1/2"
2	CB-3	CABLE250	22'-9 9/16"



SIDEWALL FRAMING: FRAME LINE E



SIDEWALL SHEETING & TRIM: FRAME LINE E
PANELS: 24 Ga. R - TBD

GENERAL NOTES:

1. Use TEK5WW screws in place of SD150 panel screws at all 10 gage members.
2. All connections to door or window jambs where the clip is not designated in the clip table / drawing are made with JC# clips (#= Girt Depth).

TRIM COLORS	
EAVE TRIM = TBD	CORNER TRIM = TBD
BASE TRIM = TBD	GUTTER =
DOOR TRIM = TBD	DOWNSPOUTS =
RAKE TRIM = TBD	
* LINER TRIM = Liner panel color	
* SOFFIT TRIM = Soffit panel color	
* ONLY APPLICABLE IF LINER TRIM OR SOFFIT PANEL IS INDICATED ON BUILDING ORDER.	

corle
ENGINEERING & CONSTRUCTION
404 Sarah Furnace Road - Imbler, PA 16855 (814) 276 - 9811

MIKE SULLIVAN STORAGE BUILDING
40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0
ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

MIKE SULLIVAN STORAGE BUILDING


REV.	DESCRIPTION	DATE


DRAWING STATUS

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: FINAL DRAWINGS.





ENDWALL FRAMING: FRAME LINE 2



ENDWALL SHEETING & TRIM: FRAME LINE 2

PANELS: 24 Ga. R - TBD

GENERAL NOTES:

1. Use TEK5WW screws in place of SD150 panel screws at all 10 gage members.
2. See detail C7A for field coping of coldform endwall column flange braces.
3. All connections to door or window jambs where the clip is not designated in the clip table / drawing are made with JC# clips (# = Girt Depth).

BOLT TABLE
FRAME LINE 2

LOCATION	QUAN	TYPE	DIA	LENGTH
Columns/Raf	2	A325	3/4"	1 3/4"

MEMBER TABLE
FRAME LINE 2


QUAN	MARK	PART	LENGTH
1	EC-1	W10X12	20'-11 1/16"
1	EC-2	W10X12	20'-11 1/16"
2	DJ-1	8X35C14	19'-0 3/4"
1	DH-1	8X35C16	16'-0"
1	G-1	8X25Z16	11'-0"
1	G-2	8X25Z16	11'-8"
1	G-3	8X25Z16	5'-3 13/16"
1	G-4	8X25Z16	18'-3 1/2"
1	G-5	8X25Z16	12'-10 3/16"
1	G-6	8X25Z16	11'-0"
1	G-7	8X25Z16	11'-8"
1	G-8	8X25Z16	5'-3 13/16"

CONNECTION PLATES
FRAME LINE 2

ID	QUAN	MARK/PART
2	4	GR08X03

FLANGE BRACE TABLE
FRAME LINE 2

VID	MARK	LENGTH
1	FB2B	1'-3 5/8"



TRIM COLORS

EAVE TRIM = TBD	CORNER TRIM = TBD
BASE TRIM = TBD	GUTTER =
DOOR TRIM = TBD	DOWNSPOUTS =
RAKE TRIM = TBD	
* LINER TRIM = Liner panel color	
* SOFFIT TRIM = Soffit panel color	
* ONLY APPLICABLE IF LINER TRIM OR SOFFIT PANEL IS INDICATED ON BUILDING ORDER.	

CORLE
BUILDING SYSTEMS
404 Sarah Furnace Road - Imbler, PA 16655 (814) 276 - 9611

MIKE SULLIVAN STORAGE BUILDING

40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0

ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

MIKE SULLIVAN STORAGE BUILDING

DRAWING STATUS


REVISION HISTORY

REV.	DESCRIPTION


FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR CONSTRUCTION: FINAL DRAWINGS.



3/26/19



ENDWALL FRAMING: FRAME LINE 5




ENDWALL SHEETING & TRIM: FRAME LINE 5
PANELS: 24 Ga. R - TBD

BOLT TABLE				
FRAME LINE 5				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-1/ER-2	8	A325	3/4"	2"
Columns/Raf	2	A325	3/4"	1 3/4"

MEMBER TABLE			
FRAME LINE 5			
QUAN	MARK	PART	LENGTH
1	EC-3	W8X10	14'-11 1/8"
1	EC-4	W8X18	27'-3"
1	EC-5	W8X10	14'-11 1/8"
1	ER-1	W10X12	24'-0 7/16"
1	ER-2	W10X12	24'-0 7/16"
1	G-9	8X25Z16	21'-5 1/2"
1	G-10	8X25Z16	22'-1 1/2"
1	G-11	8X25Z16	12'-0 13/16"
1	G-12	8X25Z16	21'-5 1/2"
1	G-13	8X25Z16	22'-1 1/2"
1	G-14	8X25Z16	12'-0 13/16"
1	CB-1	CABLE375	29'-11 3/8"
1	CB-2	CABLE375	21'-1 15/16"

CONNECTION PLATES		
FRAME LINE 5		
ID	QUAN	MARK/PART
3	2	GR08X03

FLANGE BRACE TABLE		
FRAME LINE 5		
VID	MARK	LENGTH
1	FB2B	1'-3 5/8"
2	FB1B	1'-2 1/2"



TRIM COLORS	
EAVE TRIM = TBD	CORNER TRIM = TBD
BASE TRIM = TBD	GUTTER =
DOOR TRIM = TBD	DOWNSPOUTS =
RAKE TRIM = TBD	
* LINER TRIM = Liner panel color	
* SOFFIT TRIM = Soffit panel color	
* ONLY APPLICABLE IF LINER TRIM OR SOFFIT PANEL IS INDICATED ON BUILDING ORDER.	

GENERAL NOTES:

1. Use TEK5WW screws in place of SD150 panel screws at all 10 gage members.
2. See detail C7A for field coping of coldform endwall column flange braces.
3. All connections to door or window jambs where the clip is not designated in the clip table / drawing are made with JC# clips (#= Girt Depth).

CORLE ENGINEERING SYSTEMS
404 Sarah Furnace Road - Imbler, PA 16655 (814) 276-9611

MIKE SULLIVAN STORAGE BUILDING
40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0
ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

MIKE SULLIVAN STORAGE BUILDING

REV.	DESCRIPTION	DATE

DRAWING STATUS

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: FINAL DRAWINGS.


STATE OF MAINE

T. JAMES EISENMAN, JR.
No. 9637


PROFESSIONAL ENGINEER

3/26/19


PAGE 14 OF 18




C7A FLANGE BRACE TO BYPASS COLDFORM ENDWALL COLUMN




A7 PURLIN TO ENDWALL RAFTER CONNECTION




A10 PURLIN TO RIGID FRAME ENDWALL RAFTER CONNECTION




B6 ENDWALL COLUMN TO RAFTER CONNECTION




B19 ENDWALL COLUMN TO RIGID FRAME RAFTER CONNECTION (BYPASS GIRTS)




C12 GIRT TO ENDWALL COLUMN




D12 BEARING FRAME CORNER COLUMN TO BYPASS ENDWALL GIRT




D16 RIGID FRAME IN ENDWALL TO BYPASS SIDEWALL GIRT




D27 RIGID FRAME IN ENDWALL TO FLUSH OR BYPASS ENDWALL GIRT



E6 DOOR JAMB TO FOUNDATION



G2 ROOF PURLIN TO INTERIOR FRAME RAFTER



H2 GIRT TO COLUMN - BYPASS GIRTS

NOTE #1: FIELD NOTCHING OF GIRTS WILL BE REQUIRED WHEN GIRT ELEVATIONS ARE NOT THE SAME FROM WALL TO WALL.

NOTE #1: FIELD NOTCHING OF GIRTS WILL BE REQUIRED WHEN GIRT ELEVATIONS ARE NOT THE SAME FROM WALL TO WALL.

NOTE #1: FIELD NOTCHING OF GIRTS WILL BE REQUIRED WHEN GIRT ELEVATIONS ARE NOT THE SAME FROM WALL TO WALL.

*ANCHOR BOLTS BY OTHERS

*ANCHOR BOLTS 1/2" DIAMETER

404 Sarah Furnace Road - Inlier, PA 16655 (614) 276 - 9611
MIKE SULLIVAN STORAGE BUILDING
 40'-0" x 70'-0" x 16'-0"
 DATE: 3/13/19 REVISION: 0
 ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

REV.	DESCRIPTION	DATE

MIKE SULLIVAN STORAGE BUILDING


DRAWING STATUS

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: FINAL DRAWINGS.


T. JAMES EISENMAN, JR.
 No. 9637
 LICENSED PROFESSIONAL ENGINEER




18 EAVE STRUT TO ENDWALL RAFTER LOW EAVE




J2 EAVE STRUT TO RIGID FRAME BYPASS GIRT CONDITION




K1 WALL GIRT TO DOOR JAMB




L9 DOOR JAMB TO WALL GIRT




M1 DOOR HEADER TO DOOR JAMB




Q2 CABLE BRACE / EYEBOLT




"R" PANEL SIDEWALL




CORNER TRIM




DOOR & WINDOW JAMB / HEADER TRIM



DOOR & WINDOW DELUXE JAMB TRIM



SOFFIT AT BUILDING EAVE



SOFFIT AT BUILDING GABLE

OCORLE
BUILDING SYSTEMS
404 Sarah Furnace Road - Imbler, PA 16655 (814) 276-9811

MIKE SULLIVAN STORAGE BUILDING
40'-0" x 70'-0" x 16'-0"

DATE: 3/13/19 REVISION: 0
ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

MIKE SULLIVAN STORAGE BUILDING

REV.	DESCRIPTION	DATE


DRAWING STATUS

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.


FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: FINAL DRAWINGS.


STATE OF MAINE
T. JAMES EISENMAN, JR.
No. 9637
LICENSED PROFESSIONAL ENGINEER




LOW EAVE EXTENSION TRIM




RAKE CLOSURE AT EAVE EXTENSION




RAKE TRIM AT GABLE EXTENSION (ROOF SURFACES $\leq 90^\circ$ EAVE TO PEAK)




RIDGE CAP TRIM




RIDGE CAP END CLOSURE




BASE TRIM AT BASE CHANNEL




SOFFIT TRIM AT CORNER



SOFFIT TRIM AT GABLE PEAK




GABLE AT INSET ENDWALL



W7

BYPASS ENDWALL GIRT TO BEARING FRAME RAFTER



W8

BYPASS ENDWALL GIRT TO RIGID FRAME RAFTER

CORLE
 BUILDING SYSTEMS
 404 Sarah Furnace Road - Imbler, PA 16655 (814) 276-9811

MIKE SULLIVAN STORAGE BUILDING
 40'-0" x 70'-0" x 16'-0"
 DATE: 3/13/19 REVISION: 0
 ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

REV.	DESCRIPTION	DATE

MIKE SULLIVAN STORAGE BUILDING
 DRAWING STATUS
 REVISION HISTORY


FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: FINAL DRAWINGS.


STATE OF MAINE
 JAMES EISENMAN, JR.
 No. 9637
 LICENSED PROFESSIONAL ENGINEER
 3/26/19

*SEE BOLT TABLE ON ROOF FRAMING PLAN




X6 FLUSH EAVE EXTENSION TO BEARING FRAME ENDWALL AT LOW EAVE

*SEE BOLT TABLE ON ROOF FRAMING PLAN



X7 FLUSH EAVE EXTENSION TO RIGID FRAME - LOW EAVE

*SEE BOLT TABLE ON ROOF FRAMING PLAN



X8 FLUSH EAVE EXTENSION TO ENDWALL RIGID FRAME - LOW EAVE

OCORLE
 ENGINEERING & CONSTRUCTION
 404 Sarah Furnace Road - Imbler, PA 16655 (814) 276 - 9611

MIKE SULLIVAN STORAGE BUILDING
 40'-0" x 70'-0" x 16'-0"
 DATE: 3/13/19 REVISION: 0
 ENG: IRM DWN: BJC APPD: IRM

F.O. 22636

MIKE SULLIVAN STORAGE BUILDING

REV.	DESCRIPTION	DATE

DRAWING STATUS

FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION: FINAL DRAWINGS.

STATE OF MAINE
 T. JAMES
 EISENMAN, JR.
 No. 9637
 LICENSED PROFESSIONAL ENGINEER
 3/26/19